KEYNOTES

APPLIES TO DRAWING E1.2
REPRESENTED BY n

1. REMOVE LIGHT FIXTURES, EXIT SIGNS AND EMERGENCY BATTERY UNITS IN VEHICLE BAY. REMOVE THE INDICATED TOGGLE SWITCHES. BRANCH CIRCUITS SHALL BE REUSED TO SERVE NEW DEVICES.
2. REMOVE EXTERIOR LIGHT FIXTURE. BRANCH CIRCUIT SHALL REMAIN TO SERVE NEW LIGHT FIXTURES.
3. REMOVE LIGHT FIXTURES AND TOGGLE SWITCH(ES) IN THIS SPACE. BRANCH CIRCUIT SHALL REMAIN.
4. REMOVE LIGHT FIXTURES, EXIT SIGNS, AND ENERGENCY BATTERY UNITS IN CORRIDOR. TOGGLE SWITCHES AND BRANCH CIRCUITS SHALL REMAIN TO SERVE NEW DEVICES.
5. EXISTING TOILET EXHAUST FAN SHALL BE DEMOLISHED. REMOVE CIRCUIT.
6. REMOVE EMERGENCY BATTERY UNIT AND BRANCH CIRCUIT.
7. REMOVE EXIT SIGN. BRANCH CIRCUIT SHALL REMAIN.
8. REMOVE ELECTRICAL CONNECTION AND BRANCH CIRCUIT TO EXHAUST FAN.
9. REMOVE RECEPTACLE AND WIRING BACK TO RANGE BACK TO P/BD. PROVIDE BLANK COVERPLATE FOR JUNCTION BOX. REMOVE ELECTRICAL CONNECTION AND BRANCH CIRCUIT TO RANGE HOOD. DOWNSTREAM DEVICES SHALL REMAIN OPERATIONAL.
10. REMOVE RECEPTACLE, BRANCH CIRCUIT, J. BOX, AND CONDUIT. REROUTE BRANCH CIRCUIT TO KEEP DOWNSTREAM DEVICES OPERATIONAL.
11. REMOVE ELECTRICAL CONNECTION TO CONDENSING UNITS. REMOVE BRANCH CIRCUIT BACK TO P/BD AND DISCONNECT SWITCHES.
12. REMOVE ELECTRICAL CONNECTION TO AIR HANDLIING UNITS. REMOVE DISCONNECT SWITCHES. REMOVE BRANCH CIRCUIT BACK TO P/BD.
13. REMOVE ELECTRICAL CONNECTION AND BRANCH CIRCUIT BACK TO P/BD FOR UNIT HEATER.
14. REMOVE ELECTRICAL CONNECTION AND BRANCH CIRCUIT BACK TO P/BD FOR EXHAUST FAN.

DEMOLITION LEGEND

SYMBOL	DESCRIPTION
	REMOVE DEVICES, EQUIPMENT, IN ACCORDANCE WITH THE GENERAL DEMOLITION NOTES.
	DEVICES ARE EXISTING TO REMAIN.
	WITHIN HATCHED AREAS, DISCONNECT AND REMOVE ALL ELECTRICAL MATERIALS INCLUDING BUT NOT LIMITED TO LIGHTS, DEVICES, EQUIPMENT, SPEAKERS, FIRE ALARM, COMMUNICATIONS, AND CIRCUITRY.

GENERAL DEMOLITION NOTES

A. PROVIDE ALL ELECTRICAL DEMOLITION WORK REQUIRED TO INSTALL THE WORK INDICATED. REMOVE, REROUTE, AND RECONNECT ALL BRANCH CIRCUITS THAT WILL REMAIN IN USE BUT INTERFERES WITH THE WORK.

B. REMOVE ALL EXISTING CONDUITS THAT WILL NOT BE REUSED AND WHERE THEY WILL BE EXPOSED AFTER COMPLETION. ABANDON ALL OTHERS IN THE WALLS ONLY. DISCONNECT ALL WIRING INDICATED AND/OR REQUIRED TO BE REMOVED FROM ALL POWER SOURCES. REMOVE ALL WIRING FROM ABANDONED CONDUITS AND PROVIDE BLANK COVER PLATES FOR BOXES NOT UTILIZED FOR THE WORK.

C. MAINTAIN CONTINUITY OF ALL EXISTING CIRCUITS TO REMAIN OR PORTIONS THEREOF AFFECTED BY THE WORK.

D. BEFORE DEMOLITION, VERIFY WITH THE OWNER ALL EQUIPMENT TO BE SALVAGED TO OWNER AND NOT REMOVED FROM THE SITE. FOR ALL REMAINING EQUIPMENT INDICATED FOR REMOVAL (AND NOT RELOCATED), REMOVE AND DISPOSE IN A LEGAL MANNER.

E. EXERCISE CARE IN REMOVING DEMOLITION ITEMS. REPAIR OR REPLACE ALL DAMAGE CAUSED TO EXISTING CONSTRUCTION AND EQUIPMENT TO REMAIN.

F. DRAWINGS ARE BASED UPON EXISTING PLANS AND FIELD INVESTIGATION WITHOUT DEMOLITION. VISIT THE EXISTING BUILDING AND BECOME FAMILIAR WITH ALL EXISTING CONDITIONS AND EXAMINE ALL DRAWINGS TO AVOID CONFLICTS.

G. WHERE DEMOLITION OF TELECOMMUNICATIONS DEVICES OCCUR, REMOVE CABLING NOT INDICATED TO REMAIN BACK TO POINT OF ORIGIN.

H. DEMOLITION FLOOR PLANS ARE PROVIDED FOR REFERENCE ONLY TO AID IN DEFINING THE SCOPE OF DEMOLITION WORK.

N

ELECTRICAL DEMOLITION PLAN

3/16" = 1'-0"

MOSELEYARCHITECTS
3200 NORFOLK STREET, RICHMOND, VA 23230
PHONE (804) 794-7555 FAX (804) 355-5690
MOSELEYARCHITECTS.COM

COMMONWEALTH OF VIRGINIA
HAROLD A. LANNA
Lic. No. 13231
10-15-2015
PROFESSIONAL ENGINEER

EVIDENCE STORAGE BUILDING

SMITHFIELD, VIRGINIA

PROJECT NO: 550322	DATE: OCTOBER 15, 2015
REVISIONS	
DATE	DESCRIPTION

ELECTRICAL DEMOLITION PLAN

E1.2

10/19/2015 10:58:15 AM