

Addendum #1 to RFP for Sanitary Sewer Rehabilitation Services - June 3, 2019

Proposals shall include unit prices for each item listed in the attached Scope of Services (see attached).

Scope of Services

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE
1	Mobilization of Clean & TV crew (per work order under \$3,600)	1	LS	
2	Mobilization of Lateral Lining Crew	1	LS	
3	Mobilization of Main Line Lining Crew	1	LS	
4	Mobilization of Manhole Rehabilitation Crew	1	LS	
5	Clean (light) & TV Inspection of 6" pipes	100	LF	
6	Heavy Cleaning of 6" pipes	1	LF	
7	Clean (light) & TV Inspection of 8" pipes	100	LF	
8	Heavy Cleaning of 8" pipes	1	LF	
9	Clean (light) & TV Inspection of 10" pipes	100	LF	
10	Heavy Cleaning of 10" pipes	1	LF	
11	Clean (light) & TV Inspection of 12" pipes	100	LF	
12	Heavy Cleaning of 12" pipes	1	LF	
13	Clean (light) & TV Inspection of 15" -18" pipes	100	LF	
14	Heavy Cleaning of 15" - 18" pipes	1	LF	
15	Clean (light) & TV Inspection of 21" -24" pipes	100	LF	
16	Heavy Cleaning of 21" - 24" pipes	1	LF	
17	Clean (light) & TV Inspection of 27" -36" pipes	100	LF	
18	Heavy Cleaning of 27" - 36" pipes	1	LF	
19	Install 6" x 4.5 mm CIPP liners	100	LF	
20	Install 8" x 4.5 mm CIPP liners	100	LF	
21	Install 8" x 6.0 mm CIPP liners	100	LF	
22	Install 10" x 6.0 mm CIPP liners	100	LF	
23	Install 12" x 7.5 mm CIPP liners	100	LF	
24	Install 15" x 7.5 mm CIPP liners	100	LF	
25	Install 18" x 9.0 mm CIPP liners	100	LF	
26	Install 21" x 10.5 mm CIPP liners	100	LF	
27	Install 24" x 10.5 mm CIPP liners	100	LF	
28	Install 27" x 13.5 mm CIPP liners	100	LF	
29	Install 30" x 15.0 mm CIPP liners	100	LF	

30	Install 36" x 16.5 mm CIPP liners	100	LF
31	Easement CIPP Installations, per setup A line segment is considered an easement installation when the upstream manhole is 50 feet or more from a paved surface.	1	EA
32	Internally Remove Protruding service connections	1	EA
33	Internal Reinstall of active service connections after liners are installed	1	EA
34	Internally Seal lateral connections with AV-100 grout after liner installation	1	EA
35	Clean & TV 4" / 6" Sanitary Sewer laterals from the main towards the property line. Limited to 25'.	1	EA
36	Clean & TV 4" / 6" laterals beyond 25'.	1	LF
37	Install Lateral Innerseals from the main (6" -12" diameter) up the 4" / 6" lateral two (2) linear feet.	1	EA
38	Additional 4" lateral liner installed with the Innerseal.	1	EA
39	Additional 6" lateral liner installed with the Innerseal.	1	LF
40	Install 6" Cured In Place Sectional Repair, 4 LF each.	1	EA
41	Install 8" Cured In Place Sectional Repair, 4 LF each.	1	EA
42	Install 10" Cured In Place Sectional Repair, 4 LF each.	1	EA
43	Install 12" Cured In Place Sectional Repair, 4 LF each.	1	EA
44	Manhole Rehabilitation. 1/2" cementitious Permacast MS-10,000 liner	1	VF
45	Manhole Rehabilitation. 1/2" cementitious Permacast MS-10,000 liner with Epoxy top coat	1	VF
46	Cretex Chimney Seals	1	EA
47	Stainless Steel Rainstopper Inserts	1	EA
48	By-pass pumping, 30 LF of suction hose 350 LF of discharge using a 4" pump capacity 89,000 GPD. Manhole to Manhole or Pumpstation	1	DY
49	By-pass pumping, 30 LF of suction hose 350 LF of discharge using a 6" pump capacity 2.09 MGD. Manhole to Manhole or Pumpstation	1	DY
50	Testing of liner samples per specifications	1	EA